No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
			Rs. a. p.		Rs.
22	Providing chajja cornice with R. C. C. including plastering, etc., complete	C.ft.	1 0 0	168	
23	Providing and fixing R. C. C. ventilators complete as per design	Sq.ft.	0 12 0	16	
24	Providing and fixing T. W. glazed ventilators with iron bars, etc., complete	,,	1 2 0	30	
25	Providing and fixing C. I. rain water down pipes 3" dia. including all fixtures, and painting, etc., complete	R.ft.	1 0 0	60	
26	Clearing site and levelling ground	Lumpsm			
27	Boxing girders with burnt brick in mortar including wiring and plastering, etc., complete ..	R.ft.	0 12 0	200	

R. TIPPAIYA,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 16th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 10th December 1938, 4 P.M. for extending the Middle School, at Kumsi. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for Rupees two hundred and eleven only for having credited to 17 (*a*) P. W. Deposits as earnest money, and be superscribed "Tender for extending the Middle School at Kumsi" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per the schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 211 towards the security deposit before the execution of contract agreement.

14. The cement will be supplied departmentally. The rates may be quoted only for labour charges.

Abstract estimate for extending the Middle School at Kumsi.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C.yd.	0 3 6	38	
2	Earthwork filling in basement with ½ mile lead	,,	0 7 6	20	
3	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 6 0	12	
4	Size stone in mud including bond stones at 6′ apart	,,	0 4 6	1,523	
5	Dismantling brickwork	,,	0 0 3	90	
6	Burnt brick in mud	,,	0 3 3	1,938	
7	Burnt brick in 1 : 6 cement mortar	,,	0 6 0	694	
8	Providing and fixing reinforced concrete slabs	S.ft.	0 10 0	113	
9	Burnt stone slabs 2 line dressed top and face	,,	1 1 0	151	
10	Cut stone pillars 7″ square with base and caps. 8′ high	Each	15 0 0	10	
11	Teakwood door 3″×4″ scantlings with battened shutters, iron clamps, hinges of 6″ tower bolts of 6′ and hinged wooden cleats, etc., complete.	S.ft.	1 8 0	102	
12	Teakwood windows 3″×4″ scantlings with battened shutters 4 pieces, iron bars with 4″ hinges, etc., complete	,,	1 12 0	168	
13	Teakwood sun shade	No.	8 0 0	8	
14	Teakwood wrought and put up	C.ft.	4 8 0	138.58	
15	Roofing with 1st class Mangalore tiles over teak reepers	Sqr.	24 0 0	18.30	
16	Ridge tiles set in cement mortar and pointing 1 : 6	R.ft.	0 10 0	100	
17	Removing roof and refixing with wood work for the roof of old building	Sqr.	5 0 0	22.61	
18	Removing and refixing ridge tiles in cement mortar and pointing	R.ft.	0 3 0	86	
19	Refixing valley with necessary repairs and constructing cement valleys	,,	1 0 0	20	
20	Providing and fixing new Mangalore tiles, new teak reapers and new ridge tiles, etc.	Lumpsum			
21	Flooring 3″ jelly concrete and 1½″ cement concrete and ½″ cement plaster with red colour finish and lining	Sqr.	20 0 0	7.54	
22	Flooring with Cudapah slabs over 3″ stone jelly concrete and cement pointing	,,	18 0 0	2.13	
23	Plastering with mortar	,,	3 8 0	52.65	
24	Pointing with cement mortar 1 : 3	,,	4 0 0	3.00	
25	Whitewashing 2 coats	Sqr.	0 4 6	42.81	
26	Colour washing 2 coats	,,	0 5 0	12.00	
27	Teakwood eaveboard plane 9″	R.ft.	0 8 0	153	
28	Teakwood large board	No.	15 0 0	3	
29	Teakwood pendents	,,	0 8 0	9	
30	Teakwood finials	,,	1 0 0	4	
31	Chocolate painting 2 coats	Sqr.	4 8 0	8.17	
32	Wood oiling 2 coats	,,	2 8 0	45	
33	Tarring woodwork	,,	2 0 0	3.00	
34	Supplying teakwood plank ½″ and fixing for valleys	S.ft.	0 10 0	40	
35	Supplying and fixing plain zinc sheet for valleys	,,	0 8 0	63	
36	Constructing cement valleys	R.ft.	0 8 0	63	
37	Binding walls with cement brick in mortar (1 : 6) and cement plastering 1 : 3	,,	0 5 6	66	
38	Chunam borders 6″×3″	,,	0 3 0	51	
39	Fixing bond stones of 3′×1½′	Each	3 0 0	18	
40	Miscellaneous works such as blackboards, and etc.	Lumpsum			

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notification dated 22nd November 1938.

Two serviceable pistols and three confiscated revolvers of description noted below will be sold by public auction by the District Superintendent of Police, Bangalore City, in the premises of the Central